



Joe Doud Administration Building
545 Academy Drive
Northbrook, IL 60062
847-291-2960
nbparks.org

January 20, 2023

ADDENDUM #3

Northbrook Park District

Heritage Oaks Golf Club: Golf Car Corral Fencing

Bid #2244

This addendum becomes part of and modifies, amends, and clarifies Project Manual for the above mentioned Bid. All provisions and requirements of the Project Manual shall remain in effect except as specifically changed in this addendum. Below is the list of revised items in Addendum #3.

Questions/Clarifications:

1. **QUESTION:** Is the schedule correct on Page 15, as it states Stonegate Park?

ANSWER: Yes, the Stonegate header was an error, but the schedule is correct.

i. Start Date: **March 1, 2023**

ii. Substantial Completion Date: **April 14, 2023**

iii. Final Completion Date: **April 28, 2023**

2. **QUESTION:** Will the park district be doing a private locate for the fence?

ANSWER: The contractor is responsible for calling JULIE. The park district can assist with any electrical locating. We have construction drawings and as-builts that can be utilized for other utilities. Otherwise, any other locating is the responsibility of the contractor.

3. **QUESTION:** One of the TransPort II gates is listed at 10-12' wide, but the path is 12.5' wide. Is this correct?

ANSWER: Please bid a 13-15' TransPort II gate for this location. Revised Project Scope attached.

NORTHBROOK PARK DISTRICT

PROJECT SCOPE

Unless otherwise indicated, the use of brand names in the following Specifications are used for the purpose of establishing a grade or quality.

***Bidders proposing to use an alternate that is equal to or superior to that required by the Specifications must request approval in writing to the Park District in accordance with Section X of the Instruction to Bidders.**

BASE BID

Furnish and Install:

- Roughly 325LF of 4' tall, 3 rail Montage Plus Genesis Fencing (or approved equal, see note above)
- 2 ½" square 12 gage line posts set in concrete footings
- 4" square 11 gage gate posts set in concrete footings
- One 4ft tall **13-15ft** wide opening Transport II Cantilever Slide Gate (or approved equal, see note above)
- One 4ft tall 8-10ft wide opening Transport II Cantilever Slide Gate (or approved equal, see note above)
- All material to be powder coated black
- All other and incidental work necessary to complete the work as outlined in the contract documents.

*Plan dimensions are approximate and can be adjusted slightly to accommodate standard sizing. Fence and gates should be about 1' off the existing concrete pad.

ADD ALTERNATE #1: Upgrade to Montage II Gensis, 4' tall, 3 rail.

Receipt of this addendum shall be acknowledged by signing below and including a copy within the Bid Documents.

Signature_____

Title

Company_____

Date_____